91-WOB-322

Department of Energy

0020661 9106032

P.O. Box 550
Richland, Washington 99352

OCT 0 9 1991

RECEIVED

RECEIV

Bliss, Level 1 WH Hamilton, Assignee xc: Borneman

Mr. Timothy L. Nord
Hanford Project Manager
State of Washington
Department of Ecology

Department of Ecology Mail Stop PV-11 Olympia, Washington 98504

Dear Mr. Nord:

<u>_</u>3

(N

٠.()

N

N

9

TRANSMITTAL OF ITEMS REQUESTED BY WASHINGTON STATE DEPARTMENT OF ECOLOGY (ECOLOGY) CONCERNING THE LIQUID EFFLUENT RETENTION FACILITY (LERF)

Provided for your information, is a copy of the nonconformance report (NCR W-105-13) on the Free Swell test.

The report shows that part of the soil/bentonite planned to be used in Basin 44 did not pass the initial free swell test in the construction specification. The test requires a minimum of 16 cc expansion when two (2) grams of bentonite is added to 100 ml of distilled water in a graduated cylinder.

Additional testing has been performed on the sample of bentonite taken from the suspect material to determine why the results of the swell test were slightly lower than anticipated. The outcome shows that the initial test results were low because personnel performing the test did not introduce the bentonite into the water in the graduated cylinder over a sufficient length of time. The procedure used for the measurement of free swell has been refined to assure the bentonite is introduced over a longer period of time to replicate test procedures used in industry. Based upon the refined procedure, the free swell tests now show that suspect bentonite meets the requirement.

Attachment 2 is the testing guidelines related to hydrostatic pressure testing of the double encased fiberglass piping for LERF. This information is provided for your information and satisfies a previous commitment from a LERF Project Unit Manager's Meeting.

It was necessary to develop more detailed leak testing guidelines due to problems encountered when pressure testing the 8-inch carrier piping between Basins 42-43 and 43-44. Although the piping has been successfully repaired and tested, the project plans to issue a report describing the events and recovery actions taken. The report will not be issued until Kaiser Engineers Hanford Company has resolved a potential claim against the supplier of the piping. Our investigation has shown nothing that would prevent use of the piping for service.

CORRESP()NO'ENCE

BEST AVAILABLE COPY

Ecology requested a copy of the construction schedule for LERF. Attachment 3 is an updated construction schedule previously transmitted.

Ecology requested a copy of known spare parts for LERF. Attachment 4 is the spare parts list.

Through August 1991, Ecology has received various LERF document submittals, LERF engineering change notices, and LERF vendor submittals. Attachment 5 lists the items turned over to Ecology with dates of the turnover. Additional items will be turned over to Ecology and this listing will be updated and transmitted to Ecology.

If you have any questions, please contact Ms. T. M. Hennig on (509) 376-6888.

Sincerely,

Steven H. Wisness

⊮anford Project Manager

HMT: DMW

C...

O

F = 1

17 m

إ\ي

CV

9

Attachments:

1. Nonconformance Report

2. Testing Guidelines

3. Construction Schedule

4. Spare Parts List

5. Turnover Items/Dates

cc w/att:

P. Stasch, Ecology

G. Anderson, Ecology

T. Michelena, Ecology

T. B. Veneziano, WHC

D. E. Kelley, WHC

	NONCONF	ORMANCE REPORT	Fig	=age
Project No.	W O. No.	Location (Sldg/Area)	Safety Class	NCR No.
W-105	ER0156	200E	3	W-105-13(5237-2)
Job Title				
242A Evaporator	and Purex Inte	erim Retention Basin		
Requirement(s) (Including sour	ce document numbers,	revision, paragraph, etc.)		Distribution
Specification W-105	-C4 section O2	270 Rev. 1 paragraph 2.	1.1.1	WHC
Sentonite: Sodium	Montmorillonit	e Clay meeting the foll	owing	Project Files 3
minimum standards.				PE/L. R. Tollbom 1,3
	2a to 16cc wi	en added to 100 ml of d	istilled	QA/L. R. Hall 1,3
water in graduated		. <u> 40000 00 100 mi 01 0</u>		,
was at the drammas and	<u>CV11110E1.</u>			KEH
		<u></u>		A. I. Files 1,3
		<u> </u>		Q. C. Files 1,3 ; Central Doc Cntl 3
- [43				Const Doc Control 1,2
				Engrg Doc Control 1,2
F, 45*				Perform Assmnt 1,2,3 Quality Engrg 1,3
Oescription of Nonconformance	: :		. (PM/S. L. Petersen 1,2,3
The laboratory Free	Swell test fo	or Bentonite sample #133		CE/G. C. Moist 1,2,3° CM/P. L. Rackley 1,2,3°
		en from the transportati		CM/P. L. Rackley 1,2,3 L. A. Gaddis 1,2,3
		e at 6:10 a.m. on 7-10-9		K. L. Jones 1,2,3:
		rovided laboratory test	· · · · · · · · · · · · · · · · · · ·	<u>DOE</u> A. G. Lassila 1,3
		ications. (Reference Su		•
** ***********************************		1453552). This material		
		the Fast end of the Fa		7
7		ix tickets show that 4.		•
of comix was made fro	<u>m 7-10-91 unti</u>	1 mixing ceased on 7-12	-91.	1
				}
				;
				;
				
				
				;
	11			
Originator /	Ti Ola	Daté Manager	////	/ Date
Jay 5. Vnchas/dlb	XELISI DEFECT	7-15-9/ John H. Ar	s lanian	7-16-91
Î / È		/		KE-j:364 01 (03 9.)
	DeilHCA	lue_		

NONCONFORMAN	VCE REPORT (co	ntinued)	Pa	ge _2_ of _5_
Disposition St. Use-as-is* Reject Repair* R	ework	Related X No 🗀 Y		NCE NO
Disposition instructions (generally not required for use-a	s-is and reject disposition	ons):		
	N. P.			
				•
ECN (generally requires for repair and use-as-is disposition of Yes St. No If yes, ECN No.		1 1	1 wic 6-4-11	
If no, provide explanation: <u>Procedure for the</u> Chen-Northern and now replicates	e measurement o supplier's tes	of free swell is	has	been refined by
Disposition Justification (if applicable):	<u> </u>			
A refined procedure to test fre	e swell of ben	tonite requires a	minimum dura	tion of
4-hours, to compare with tests	done by manufa	cturers. As per	the report by	y Chen
Morthern Inc. tests based on re	fined procedur	e yield a minimum	swell of 16	cc per
2 gms. Attached is a cooy of r	eport. Tests	done by manufactu	rer and other	r independent
labs indicate that Sample #1339	meets the req	uirements and the	soil-benton	ite mix
produced with bentonite recrese	nted by the sa	mole is acceptabl	e	
Approval/Concurrence:				
Construction Approval	,	Custo	mer Projects Approv	
CF/CM Engineer N/A.		Custo ZATILL Engineer XATILL	-7.5 va. 1 Tele	8-2-91 Cu Date <u>8-6-9</u>
Field Quality Engineer N/A	Date	CA Xama	2.14=1X	same <u>G-5-9</u>
Design Engineer 7. And 1	Date 7/3=/11	DOE Win 5 Chin	ha Telmin	sate <u>8-5-9</u> 1
Lead Engr. Discol Mgr. T. Andrew	7/30/41	ALANI(ASME) N	<u> </u>	Date
Quality Engineer D. D. J. J. J.	Date 8/1/9/	KEH Code Engr. N	19	Date
Safety Engineer Dlundson	Date <u>7-3/-9/</u>	Environmental 7. 4	udd	Date 7/36/9/
Ciosure		Originato	r or Representative	Date
		91.	I Dole	5-6-91
Otner (Explain)		Superviso	1 July Jenny Land	C Date
		<u> </u>	JESCHNIAN	8-5.91

Chen@Northern,Inc.

W-105-13 (5237-2)
Pg. 3 of 5
Attended to RECEIVE

. -

JUL 31 199

Parakaman Antue Parakan Parakan yang paraka

PROJ. MGMT

507547-1671 107547-1673 Factorine

July 29, 1991

Kaiser Engineers Hanford Company P.O. Box 888
Richland, Washington 99352

ATTENTION: Mr. Tom Ambalam, P.E.

SUBJECT: Free Swell Test Results, July 26-27, 1991

Bentonite Sample # 1339;

W-105 Project

Gentlemen:

In

~

. O

€ \

N

0

At your request, we have performed additional testing of bentonite sample Number 1339. This testing was performed for three purposes:

- 1. To determine the effect of time of bentonite addition on free swell test results.
- 2. To refine the test method.
- 3. To determine if the sample meets the minimum specified free swell of 16 milliliters after a 16 hour period.

Initial test results indicated that the subject sample did not meet the minimum specifications for free swell. Subsequent multi-operator testing indicated that the subject material would generally meet the minimum free swell specification, but that there were variances in test results which were inexplicable; and, furthermore, there was no explicable trend to the test results.

On July 25, 1991, representatives of Kaiser Engineers Hanford Company, the LOESS Group, and Chen-Northern, Inc. met to discuss the available test data.

The test method used to determine free swell is not specific regarding the rate at which the 2 gram sample is introduced into the water. Initial testing was been performed using a 1.5 to 2 hour application time.

Based on a discussion of clay mineralogy, it was decided to perform a series of free swell tests by varying the amount of time the requisite 2 gram bentonite sample was introduced into a 100 milliliter graduated cylinder.

Four samples were tested at intervals of 1.5 hours, 3 hours, 4.5 hours, and 6 hours time for addition of 2 grams of bentonite. The

Andrew we wan HIH request equent.

Kaiser Engineers Hanford Company July 29, 1991 Page 2 of 2

results are tabulated below.

HOURS FOR APPLICATION	1.5	3.0	4.5	6.0
Free Swell, Milliliters	16.5	18.0	19.0	19.0
	15.5	17.5	17.0	18.0
	16.5	17.0	17.0	17.5
	16.0	17.0	18.5	17.0

The test data were plotted using the proprietary program "GRAPHER" by Golden Graphics (attached). A best-fit curve using a power function was applied. The power equation calculated by the program is:

$$0.077615$$

Y = (X) * 15.748413

With regard to test result significance for the W-105 project, two observations of this tests data were made:

- 1. Even with 1 operator performing the same task at a similar time interval, there is data scatter.
- 2. The general trend (and best-fit curve) of the test data indicate that, with additional time for application of bentonite to water, the amount of free swell increases. It is known that at some amount of time, the amount of free swell will become asymptotic (not increase).

Based on these results, it is our opinion that given a longer application time than was apparently initially employed in test operation, the material meets the minimum job specification of 16 milliliters free swell.

Respectfully Submitted, CHEN-NORTHERN, INC.

S

(\\

CV.

O


Brian J. Williams, P.G. George rical Engineer

Dee J. Burrie, P.E. Division Manager

cc: Larry Gaddis, P.E., KEH Stave Peterson, KEH

Attachment: Bentonite Free Swell Data Plot

Chen Northern, Inc.



Attach-ent 1

O

"PIPE IN A PIPE" GUIDELINES FOR HYDROSTATIC TESTING

The following is a step-by-step of activities to complete a double-encased pipe "hydro" test. Actual field conditions or circumstance may require deviation (see Page 3 for a detailed schematic of the testing apparatus).

Assure a starting position of all valves closed carrier and encasement.

1. Filling and Pressurization of Carrier Pipe

- A. Pressure Relief Valve (PRV) to be set 130 psig to 140 psig
- B. Open valves on the carrier pipe in the following sequence:
 - 1. F High Point Vent
 - 2. A Supply (Main)
 - 3. B 3/4" Supply (8" is now filling)
 - 4. C 1/4" PRV Side

Note: B and C may be opened simultaneously.

Constant monitoring of filling operation and gauges is required.

When the carrier system is full (all air vented), close valves F and 8.

Proceed to pressurize the carrier with the in-line pressure device. Attain approx. 120 psig.

Close valves C and A. The carrier line is now pressurized and isolated. Monitoring of gauges during Step 2 (encasement filling) will assure pressure differential.

All valves should still be in the closed position from Step 1.

2. Filling and Pressurization of Encasement Pipe

- A. Pressure Relief Valves set to 120 psig
- B. Open valves on the encasement side in the following sequence:
 - G High Point Vent
 - A Main Supply
 - 3. D 3/4" Encasement Supply (encasement is now filling)
 - 4. E 1/4" PRV Side

Note: D and E may be opened simultaneously.

Again, monitoring of gauges during the filling operation is required to assure encasement pressure does not exceed carrier pressure when the encasement system is full (all air vented).

Close Valves D then G.

Proceed to pressurize the encasement with the in-line pressure device. Attain a minimum 90 psig.

Close Valves E and A.

The system shall be held in this condition for a minimum of 10 minutes and until all connections have been inspected.

CAUTION - DEPRESSURIZATION

NOTE: IT IS IMPERATIVE THAT ENCASEMENT PRESSURE IS RELIEVED FIRST!

When the inspections have been completed, proceed with de-pressurization in accordance with the following:

1. Encasement high point vent shall be opened first and remain open thru all draining activities.

Vaive G

♥

₩ 40

N

N

O

- A. Verify pressure has been relieved by visual of system gauges prior to Step 2.
- 2. Carrier High Point Vent shall be opened and remain open during all draining activities.

Valve F

- A. Verify pressure has been relived by visual of system gauges.
- 3. Proceed with normal draining activities.

Again, monitoring of gauges during the filling operation is required to assure encasement pressure does not exceed carrier pressure when the encasement system is full (all air vented).

Close Valves D then G.

Proceed to pressurize the encasement with the in-line pressure device. Attain a minimum 90 psig.

Close Valves E and A.

The system shall be held in this condition for a minimum of 10 minutes and until all connections have been inspected.

CAUTION - DEPRESSURIZATION

NOTE: IT IS IMPERATIVE THAT ENCASEMENT PRESSURE IS RELIEVED FIRST!

When the inspections have been completed, proceed with de-pressurization in accordance with the following:

1. Encasement high point vent shall be opened first and remain open thru all draining activities.

Valve G

C,

1

N


N

9

- A. Verify pressure has been relieved by visual of system gauges prior to Step 2.
- 2. Carrier High Point Vent shall be opened and remain open during all draining activities.

Valve F

- A. Verify pressure has been relived by visual of system gauges.
- 3. Proceed with normal draining activities.



Hydrostatic Test Set-up Diagram

ġ,

DOCUMENT TRANSMITTAL

Oace: August 8, 1991

ro: L. R. Tollbom R3-30

rom: S. L. Petersen

E6-50

Project/York Order Number: W-105

Project/Work Order fitte: 242-A Evaporator Interim Retention Basins

Scaject:	Hydrotesting Guidelines For Double Encased Fi	iberglass Pipe	
No. of Copies	Company and Distribution	Mailing Acgress	,
00E 1	A. G. Lassila	A5-18	
-i- T CHHC	R. J. Julian L. R. Tollbom	RI-48 R3-30	
C. C.	R. T. Franch S. L. Petersen Engineering Document Control Transmittal Clerk	€5-61 €6-50 €6-52 €5-52	

#9 ~ #	Attached Are	<u> </u>	Purpose		Comments	7	Please
[]	Prints	[x]	Information	[]	Preliminary	[]	Comment
[]	Specifications	[X]	Action	[]	Unchecked		Approve
[]	Traveters	[]	enusangi2		Checked	[]	Oestray Previous (saue
(1)	Appr. Oata	[]	Upgate	[x]	Finat		Return Previous (ssue
[]	Forms	[]	Review	[]	Approved	[X]	Nace Revision
[]	Library Macerial	(1			Marking Capies	[]	Hate Halas
[X]	Procedures	[]		(1	Controlled Copies	[X]	file
[]	Other:		·	7 (1	Other:		

Occupent Numbers, Titles, and/or Comments

W-105

Hydrotesting Guidelines for Double Encased Fiberglass Pipe, KEH Letter Number W-105-113, Dated 8/07/91.

SLP/sjm

KEH 0001.00 (12/89) (EF) KEF003 Document Transmittal

KAISER ENGINEERS HANFORD

W-105-113

KAISER ENGINEERS HANFORD COMPANY POST OFFICE BOX 388 RICHLAND, WASHINGTON 99352

REG. NO. KAISEEH1348M

August 7, 1991

Mr. L. R. Tollbom, Project Engineer Evaporator Restart Projects Westinghouse Hanford Company P. O. Bax 1970 Richland, Washington 99352

Dear Mr. Tollbom:

3

 \bigcirc

0

PROJECT W-105 - HYDROTESTING GUIDELINES FOR DOUBLE ENCASED FIBERGLASS PIPE

Enclosed are the guidelines for Hydro Testing of Double Encased Fiberglass Pipe that will be attached to Process Control Packages (PCPs) #4, 11, 13, and 15. The steps detailed in the attachment were closely followed in the successful retesting of the two (2) 8 N I2 Sections. I understand this letter will be transmitted to the Washington Dept. of Ecology (WOOE) and fulfills KEH's commitment to provide a detailed procedure for hydrotesting double encased pipe systems.

Please feel free to contact me at 376-7216 if you have any questions.

Thank you.

S. L. Petersen, Project Manager Evaporator Restart Projects

SLP:aks

Attachment

cc: R. T. French

R. J. Julian - WHC

A. G. Lassila - DOE

 \mathcal{N}

 \sim

15 22 29 5 12 19 26 MILESTONES K35 START LINER-BASIN #42 M36 COMPLETE LINER-BASIN #42 TF -20 MAT START LINER-BASIN #43 TF -20 0.5 MS9 COMPLETE LINER-BASIN #43 TF -20 0. M40 START LINER-BASIN #44 TF -19 0. M41 CONSTRUCTION COMP BASIN \$42 \$ \$43 TF -18 0.5 MAS COMPLETE LINER-BASIN #44 TF -19 0.3 M43 START COVER-BASIN # 42 TF -15 0.5 H44 COMPLETE COVER-BASIN #42 TF -15 0.4 M45 COMSTRUCTION COMP BASIN #44 TF -18 M46 START COVER-BASIN #43 TF -20 M47 COMPLETE COVER-SASIN #43 TF -20 0.5 MAB START COVER-BASIN #44 TF -19 0.3 M49 COMPLETE COVER-BASIN #44 TF -19 0.5 MEO TURNOVER BASIN #42 E #43 TF -20 0% M51 TURMOVER BASIN #44 TF →19 CONSTRUCTION FORCES 0182 ATP FOR BASIN #42 TF 14 0.% 0172 ATP FOR BASIN #43 TF 9 0.5 0:82 ATP FOR BASEN #44 TF 22 0% TF 0 DE: BACKFILL/TESTING EVAPORATOR TO FENCE TF 58 95% 056 459UTLT/00C TURNOYER BASINS #48 6 #43 TF -20 0% 057 FINAL AS-BUILT & DOC TURNOVER TF -19 0% 058 BACKFILL/TESTING X-COUNTRY TF 63 90% OBD VECH/ELECT/INSTR #42 BASEN TF -10 0.5 081 PECH/ELECT/INSTR BASIN 143 TF -15 0% 082 MECH/ELECT/INSTR BASIN #44 TF 12 0% 084 COATING CATCH 9452N #43 TF -15 0.5 086 COATING-CATCH BASIN #42 TF -10 0% 087 CATCH BASIN COATING #44 TF 12 0% "Sheet 1 of 2"

Attrachment 3 to letter 91-WC8-322

	1991
	MAY
	FIXED PRICE
TF 40 85%	0050 SUB-VITTALS (LINERS)
TF -14 86%	0070 CATCH BASTN #42 SURVEY/EXC/FTC.
TF 5 0%	0072 CURING-CLTCH BASIN 142
100%	0074 RING MALL BESIN #42
TF -14 0%	C110 CATCH BASIN #43
TF 0 0%	0112 CURING-CATCH BASIN 443
100%	0194 RINE WALL BASIN \$43
TF 12 0%	0120 CATCH BASIN 644
TF 27 0%	0122 CURTING-CATCH BASIN #44
TF 12 10%	012- RIKS WALL-BASIN #44
TF -19 0%	0130 LINEP BUSIN FEE
ĭF −19 0%	0132 C-2 PIPINS EASIN #44
IF -20 0%	0140 LINER #43 RASIN
iF −20 0%	0142 C-2 PIPING BASEN #43
F -20 CK	0150 LINES 5781K 845
F -15 0%	0:52 C-2 PIPING BASIN #42
F -15 0%	D:50 CONER #42 BASIN
F -20 0%	0170 COVER 648 B157N
F ~19 0%	0180 CCVER 5:514 444
F -9 5%	275 C-5 ADIOS PAVINS FENCES, LIFETING
F -9 7%	225 CHANGE TRAILER PROCVINSTALL
	OLE SOURCE-COVERS
F 1 72%	C216 COVER SUBVITTALS/SUBVITT REVIEW
F 0 89%	57 AUCIT
0 0%	0220 COST PRICE ANALYSIS
Activity	Bar/Early Dates KAISER ENGINEERS HANFORD Sheet 2 of 2 KAISER ENGINEERS HANFORD ACTIVITY
Critical Progress	Bar LIQUID EFFLUENT RETENTION FACTUATY
Tanget D	W105/BASELINE VS CURRENT/REV 6
imavision PC EN	Project Start: 1DEC69 Project Finish: 10FE392 Project Finish: 10FE392 Data Date: 14SEP91 Plot Date: 13SEP91

SPARE PARTS LIST FOR LERF

As of 8/28/91 * Indicates items changed since last update.

Thermostat control for heat trace system

Tracetek sensor cable with plug-in

- 3 inch castiron butterfly valve
- 4 inch castiron butterfly valve
- 8 inch castiron butterfly valve

Geoguard shallow well sampler pump

Medical grade silicone 3/8 inch tubing

- 1.5 hp Berkley leachate submersible pump
- 5 hp Berkley leachate submersible pump

Ashcroft pressure switch model B400

Ashcroft pressure switch model B700

Lengths of fiberglass pipe and assorted fittings

LERF DOCUMENT SUBMITTALS TO ECOLOGY

As of 6/06/91

* Indicates items changed since last update.

Engineering Study - Submitted

Functional Design Criteria - Submitted

Conceptual Design Report - Submitted

Sitework Specification C-I - Submitted

Basin Liners and Basin Piping Specification C-2 - Submitted

Basin Cover Specification C-8 - Submitted

Draft Groundwater Monitoring Plan - Submitted

Design Specifications and Drawings as developed - Submitted

Soil/Bentonite Mixing and Placement Specifications C4 - Submitted

Notice of Intent - Submitted

SEPA documentation - Submitted

Part A Permit Application - Submitted

Final Groundwater Monitoring Plan - To be submitted

*Engineering Change Notices - Being Submitted as prepared

Part B Permit - To be submitted

CQA Plan for construction - Submitted

*Waste Analysis Plan - Submitted

*Inspection Plan - Submitted

*Contingency/Emergency Plan - Submitted

*Training Plan - Submitted

*Preparedness/Prevention Plan - Submitted

Soil/Bentonite repair procedures - Not Required To be Submitted

Cover performance standards and air quality plans - To be Submitted

C

0

ECN NUMBER	DATE RELEASED	DATE SUBMITTED
W-105-72 W-105-3 W-105-4 W-105-5 W-105-7 W-105-7 W-105-13 W-105-13 W-105-14 W-105-14 W-105-19 W-105-22 W-105-23 W-105-24 W-105-24 W-105-33 W-105-37 W-105-38 W-105-37 W-105-38 W-105-39 W-105-39 W-105-39 W-105-39 W-105-40 W-105-40 W-105-51 W-105-55 W-105-55 W-105-57	3-11-91 5-11-90 5-11-90 5-11-90 6-5-90 5-22-90 5-29-90 7-6-90 11-12-90 7-13-90 8-6-90 7-23-90 2-17-90 7-25-90 12-5-90 8-22-90 8-22-90 8-22-90 8-30-90 10-25-90 10-3-90 9-19-90 9-19-90 9-19-90 10-4-90 11-12-90 11-12-91 1-2-91 1-2-91 1-2-91 1-21-91 1-21-91 1-21-91 1-21-91 1-21-91 1-21-91 1-21-91 1-21-91	4-11-91 5-1-91
W-105-58	1-29-91	5-1-91
W-105-60	2-21-91	5-1-91
W-105-61	2-21-91	5-1-91
W-105-62	2-5-91	5-1-91
W-105-63	1-29-91	5-1-91
W-105-64	3-5-91	5-1-91
W-105-67	2-8-91	5-1-91
W-105-68	3-4-91	5-1-91

C:\WPDATA\LERF\LETTERS\CONSOLID.ATE

W-105-69	2-8-91	5-1-91
W-105-73	3-12-91	5-1-91
W-105-74	3-4-91	5-1-91
W-105-75	3-12-91	5-1-91
W-105-76	3-12-31	
W-105-77	4-4-91	5-1-91
,		5-1-91
W-105-78	4-3-91	5-1-91
W-105-79	4-4-91	5-1-91
W-105-80	3-27-91	5-1-91
W-105-81	4-3-91	5-1-91
W-105-82	4-3-91	5-1-91
W-105-83	4-3-91	5-1-91
W-105-84	4-3-91	5-1-91
W-105-43	3-21-91	6-3-91
W-105-65	4-17-91	6-3-91
₩-105-70	5-15-91	6-3-91
W-105-85	4-17-91	6-3-91
W-105-86	5-8-91	6-3-91
W-105-88	4-12-91	6-3-91
W-105-90	5-2-91	6-3-91
W-105-91	5-15-91	6-3-91
W-105-92	5-17-91	6-3-91

LERF VENDOR SUBMITTALS TO ECOLOGY

As of 6/3/91

ITEM REQUESTED

DATE DELIVERED

Bentonite Carpet Liner

High-density Polyethylene Liner

Geotextile Fabric

5/17/91 FAX

Drainage Net (Synthetic Media)

Very-low-density Polyethylene Cover

Basin Piping

Elastomeric Sealant Pipe fittings bonding

Catalog data of piping system

components

Certified results of Mfgs

pressure tests

Coatings, List of Materials

6/3/91 Unit Manager's Meeting

Plumbing

 \sim

 \bigcirc

*

· 🔿

O

Leachate pumps Transfer pumps

Valves

- MOV-W60-03 Ball Valve

6/3/91 Unit Manager's Meeting

- 8 inch hand operated

Butterfly Valve

6/3/91 Unit Manager's Meeting 6/3/91 Unit Manager's Meeting

- Butterfly Valves

- Hand operated Centerline

Butterfly Valves

6/3/91 Unit Manager's Meeting

Accessories

- MOV-W60-03 Actuator - Pressure Gage Y-103 6/3/91 Unit Manager's Meeting

- Pressure Switch Y-104

6/3/91 Unit Manager's Meeting 6/3/91 Unit Manager's Meeting

- Piston Meter Y-105

6/3/91 Unit Manager's Meeting

- Strainer and Cross Reference

for P.D. Meters (Y-105)

6/3/91 Unit Manager's Meeting

Operation and maintenance manuals

		_				_
F	ec	÷	٣Ť	^	2	Į
				•	а	- 1

Leak sensing and locating cables

Level detection system

- Leak Detection System Y-10 6/3/91 Unit Manager's Meeting

Transformers

- 60 KVA Transformer 6/3/91 Unit Manager's Meeting

Accessories

- Breakers, Receptacle, Vapor Fixture

6/3/91 Unit Manager's Meeting

- Mini Power Center and Motor Controllers

6/3/91 Unit Manager's Meeting 6/3/91 Unit Manager's Meeting

- Mini Power Zone Supply

Cables

??

CORRESPONDENCE DISTRIBUTION COVERSHEET

Author

Addressee

Correspondence No.

S. H. Wisness, RL

T. L. Nord, Ecology

Incoming: 9106032

TRANSMITTAL OF ITEMS REQUESTED BY WASHINGTON STATE DEPARTMENT OF ECOLOGY (ECOLOGY) CONCERNING THE LIQUID EFFLUENT RETENTION FACILITY (LERF)

INTERNAL DISTRIBUTION

Approval	Date	Name	Location	w/att
	٠	Correspondence Control	A3-01	
		R. J. Bliss, Level 1	B3-04	
		L. E. Borneman	B2-35	
		L. C. Brown	H4-51	
		C. J. Geier	H4-57	
•: .		W. H. Hamilton, Assignee	N3-10	•
		H. D. Harmon	R2-52	
		K. R. Jordan	B3-51	
	•	M. K. Korenko	B3-08	
		R. E. Lerch	B2-35	
		P. J. Mackey	B3-15	
		H. E. McGuire	B3-63	
		L. L. Powers	B2-35	
		T. B. Veneziano	B2-35	
		R. D. Wojtasek	B2-15	
		EDMC	⁻ H4–22	

